### 風險評估與管理 - 捷運建設的經驗

### **Risk Assessment and Management**

#### - Lessons Learnt in Metro Projects



闕河淵 H.Y. Chuay BSc MSc PhD PE FICE

13 Nov 20

# 35年捷運建設: 1986 - 2020

- 可行性研究,規劃,基本設計,細部設計, 施工,整合測試,通車履勘
- 業主,設計顧問,監督顧問,土建營造廠
   商,機電系統廠商
- 傳統設計後施工, Design-Build, Turnkey, BOT

# >150 km Metro Projects

- MRT, MCT, LRT, 傳統客運/貨運鐵路
- 用地取得,聯合開發
- 獨立驗證與認證
  - Independent Verification & Validation, IV&V
- 價值工程 Value Engineering, VE
- 風險管理 Risk Management

### 綱要 Outlines


投入風險管理領域之由來 What to attract attention?
 風險管理作業 Risk management process
 風險管理案例 Cases – Planning/Design, Construction
 國際風險管理標準 International standards

#### **Major Accidental Events in Taiwan and Overseas**

1994(April)	TRTS-CH221: Excessive ground subsidence during segment replacement in the interface of bored tunnel and vent shaft		
1994 (Oct)	Heathrow Express Rail Link: Collapse of a NATM tunnel		
1994(Nov)	TRTS-CN252: Ground loss induced by piping in deep excavation of an underground station		
1995(April)	TRTS-CN261: Ground loss during TBM-launching		
1995(July)	TRTS-CN262: Excessive ground loss during TBM-docking		
	TANEEB Suei-shan Tunnel: Series of accident during TBM & NATM tunnelling		
2002(Aug,Nov)	THSRC-Hu-ko Tunnel: Ground loss during NATM tunnelling		
2003(Feb)	TRTS-CD266: Ground loss during TBM-docking		
2003(May)	KRTC-LUO04: Excessive ground loss during TBM-docking		


#### 2003(July) Shanghai Metro 4: Tunnel collapse during the excavation of a cross-passage 2003(Aug) KRTC-001: Ground loss induced by piping due to defective diaphram wall during the excavation of an underground station 2003(Aug) TRTS-CK570C: Flooding due to a gap btwn the river bank and a pump station 2004(April) Singapore LTA-MRT Circle Line: Collapse of 33m deep excavation of a cut-and-cover tunnel 2005 (Dec) KRTC-LUO09: Excessive ground subsidence during the excavation of a sump inside a cross-passage 2007(Jan) Sao Paulo Metro-Linea 4: Collapse of a NATM tunnel

2008(Nov) Hanzho Metro – Line 1: Collapse of 16 m deep excavation





- KL-MRT2 (2016)
  - Deductible: NT\$7-10m
  - Limit of indemnity: NT\$2,200m
- 台北捷運萬大線 (2014)
  - 自負額:NT\$2-5m
  - 賠償上限:單一事故NT\$100m (區段標上限NT\$300m)



#### 捷運工程保險和重大施工意外之統計資料

#### Problems :

- Nightmare for clients or contractors

- No offer of insurance policy by insurers
- High premium but very limited coverage


(low frequency but severe consequence)

- Concerns by insurers

- Frequency of accidents
- Severe consequence

#### Joint Code of Practice for Risk Management of Tunnel Works in the UK

- Discussion at ICE, London in July, 2002 about the "JCoP for the procurement, Design and Construction of Tunnels and Underground Structures in the United Kingdom"
- Jointly produced by Association of British Insurers and British Tunnelling Society in 2003
- Pre-requisite for insurance





ITA (Intern'l Tunnelling Association) Working Group 2 (2004): Guidelines for tunnelling risk management

ITIG (Intern'l Tunnelling Insurance Group) (2006):A Code of Practice for Risk Management of Tunnel Works- Supported by ITA and Intern'l Association of Engineering Insurers






## •生命,財務,時間,政治

•施工,營運

• 規劃,設計,施工階段

The Risk Assessment Process







#### Risk Level Matrix

★ Frequency of occurrence of a hazardous event	Risk Levels			
Frequent	Undesirable	Intolerable	Intolerable	Intolerable
Probable	Tolerable	Undesirable	Intolerable	Intolerable
Occasional	Tolerable	Undesirable	Undesirable	Intolerable
Remote	Negligible	Tolerable	Undesirable	Undesirable
Improbable	Negligible	Negligible	Tolerable	Tolerable
incredible	Negligible	Negligible	Negligible	Negligible
	Insignificant	Marginal	Critical	Catastrophic
	Severity Levels of Hazard Consequence			

計畫管理文件架構




#### **Project Organisational Structure**




### Case History I


- Kaohsiung MRT R&O Lines LUO09 Recovery Plan







#### LUO09 Recovery Plan



0





- 細沙或沉泥/地下水位高
- 設計變更:二個聯絡通道位於地下道二端,變更為一個位於地下道中央
- 深度增加
- 聯絡通道上方地下道成為土壤改良作業 的障礙
- 集水井設於聯絡通道內



#### Case History 2: Planning/Design Stage

#### **Necessity of cross-passages in bored tunnels**



#### **Prescriptive criteria vs Performance-based approach**

- NFPA 130: Standard for Fixed Guideway Transit and Passenger Rail Systems (2007)
  - < 6.2.2.3 Means of egress (Cross-passageways): Not farther than 244 m (800 ft) apart
  - < 1.4 Equivalency: New method, material or device equivalent to or superior to the requirements of this standard with respect to fire and life safety

< 4.2.2 Goal: Minimum requirements for those instances where "noncombustible materials are not used"







Quantitative Risk Assessment, QRA

## Fault Tree Analysis, FTA 災害樹分析

- Data base from UK EMU operation of 34 years
- Data from KCRC EMU operation of 14 years
- Internal fire event: 20 month return period
- External fire event: 15 month return period



.



w#1.56e-8 w=1.97e-9 w=1.61e-10 w=1.26e-10 w=1.34e-11 w=1.47e-10





### Event Tree Analysis, ETA


事件樹分析


#### **Event Trees**


Fire in Passenger Carriage In Single Track Tunnel (Internal Fires)
















#### Structure of Tunnel Fire Risk Model




#### Standard Fire Curve for DFRA and QRA Tunnel Fire Analysis



Structure of KCRC TFRM





#### Trend Graph for Individual Equivalent Injury Risk

#### Necessity of cross-passages in bored tunnels (Kowloon Canton Railway 2003)

- Deterministic Fire Risk Assessment of Tunnel fires
  - < Principle: Passengers to walk away in tunnel fire and reach a place of safe passage
  - < Evacuation strategy of passengers in tunnel fire
    - Transverse vs Linear evacuation routes
      - Duration of evacuation against various cross-passage spacing
    - Evacuation through side doors or end doors
  - < Key factors in the safety of evacuation
    - Evacuation in the correct direction
    - Correct operation of the ventilation system

Possible Solution: Transverse vs. Linear evacuation

#### Necessity of cross-passages in bored tunnels (Kowloon Canton Railway 2003) Results of analyses

- -No measurable safety benefit provided by a closely spaced cross-passage configuration
- Vital safety factors: Initiation of evacuation in the correct direction & Correct operation of the ventilation system
- Simple procedure for linear evacuation providing better crowd control and reducing the likelihood of accidents

## Case History 3


- Kuala Lumpur MRT Line 2
  - Chan Sow Lin Station, CSLS

FEATURES ALREADY EXPOSED in Chan Sow Lin excavation.

Multiple caves and cavities were unearthed during excavation. Extreme Karst condition exhibit very variable combination of black organic material infills to highly weathered rock.



## Geological Conditions




#### Ground Investigation:

- 1. Soil Investigation
- 2. Drilled Holes for Curtain Grouting Surrounding Station Perimeter (2m to 4m spacing c/c)
- 3. Bored Pile Drilled Hole
- 4. Microgravity Survey
- 5. Borehole Televiewer
- 6. Rock Mapping on Rock Face


## **Geological** Conditions

Deep valley cutting across Chan Sow Lin Station footprint shown by microgravity survey (in blue) and SI data/piling record/grouting ecord

MODEL




## Site Plan



Station Information								
Length	200 m							
Width	21.6 m							
Depth	40 m							
Entrance	3 nos							
Linkway to LRT	l nos							
No. of Floors	5							

## Station Configuration




#### Example of What Could Go Wrong

Example of localized ground loss (rock slip) due to unforeseen rock joint formation behind exposed rock face.

Despite extensive soil investigatio n and geophysics work were





#### **Risk Rating Matrix**

	0	C		IMPACT SEVERITY											
		<u> </u>	Risk Area	1	2	3	4	5							
				Minimal	Minor	Moderate	Major	Severe	Catastrop						
	Ĕ		Financial	<1 mill	>1 mill <u>&lt;</u> 5 mill	> 5 mill <u>&lt;</u> 10 mill	> 10 mill <u>&lt;</u> 20 mill	> 20 mill	> I bill						
	CAPACITY		Safety	None	First aid required	Medical treatment required	Serious injuries	A fatality case							
	5		Programme	< 4 wks	> 4 wks <u>&lt;</u> 8 wks	>8 wks <u>&lt;</u> 12 wks	>12 wks <u>&lt;</u> 16 wks	>16 wks							
	IMPACT		Third Party Impact		Minor damage some repairs required	Moderate to high damage requires specialist to repair	Significant / permanent damage	Widespread, substantial/ permanent damage							
	N		Environmental Impact	spoils at works area	Slight contamination of spoils at works area - some precaution's necessary result in slight delay	into public space causing public nuisance/discomfort	Major source of contamination causing adverse public health & well being	Catastrophic environmental damage							
ПКЕПНООД	Almost Certain - happens 5 frequently (more than 10 times within the project)			5	10	15	20	25							
		4	Very Likely - could happen frequently (more than 3 times within the project)	4	8	12	16		20						
	3		Likely - could happen occasionally (less then 3 times within the project)	3	6	6 9 1		15							
		2	Unlikely - could happen rarely (1 time within the project)	2	4	6	8	8 10							
		1	Very Unlikely - probably will not happen (has never occurred)	1	2	3	4		5						

Low Medium



48

#### **Risk Assessment**

Top 2 risks anticipated due to DUKE3 piling
work are:
Safety related to rock slip
Impact to programme/cost

#### Risk Assessment – Safety Related to Rock Slip

## Likelihood: Category 2/3 [Risk Rating Matrix]

- Site investigations were carried out according to best practice.
- Geological mapping was carried out during excavation and the design of rock bolts and shotcrete was done accordingly.
- However, geological conditions can not all be fully exposed.

# Impact Severity: Category 5 [Risk Rating Matrix]

• 50-150 workers in any time; therefore, the consequence can be catastrophic if a rock slip occurs.

## Level of Risk: Severe (Cat 5) x Unlikely/Likely (Cat 2/3) = High (10-15)

## Mitigation Measures


#### By DUKE 3

No piling work until the completion of concourse sla


• One pile at a time after the completion of concourse slab.

#### By MGKT

• Remove the workers 20m to either side of piling point. No activity in the 40m cordoned-off zone during active piling.




For example: when P42-L piling work is on-going, MGKT's no-work zone shall be as highlighted.



Proposed 2 Level Structural Completion of Station Box

Structural Completion until Chateurse Level Slab Level


 After the completion of concourse slab, the remaining rock face height is still approx. 20m.



CSLS Box Cross Section

52


 $\mathbf{\mathcal{C}}$ 




#### **Case History 4: Design Stage**

#### Design of R10 Cofferdam (Kaohsiung MRT Project)

- Risk assessment: Hazard identification and mitigation measures
  - < 140 m in diameter and 20/27 m deep with no strutting system in urban area
  - < Hoop pressure = Ground water pressure (80%) + Earth pressure (20%)
  - < Verticality of diaphragm wall
  - < Glass-fiber re-bar for TBM-launching
  - < External excavation after the concreting of the circular structure
  - < Geotechnical monitoring system





# Risk assessment: Hazard identification and mitigation measures

- < 140 m in diameter and 20/27 m deep with no strutting system in urban area
- < Hoop pressure = Ground water pressure (80%) + Earth pressure (20%)
- < Verticality of diaphragm wall
- < Glass-fiber re-bar for TBM-launching
- < External excavation after the concreting of the circular structure
- < Geotechnical monitoring system



				a)		Pre RCM				Measures			Post RCM					
Period	Phenomenum		ence	poo	Construct Environ ion Safety ment		Cause			charge	poo	Construct ion Safety			uiron ent			
Pel	Large scale	munemone scale lufinence		Influ	S R S R		Contents red Contents red Contents		Lidelihood	s	R	s	R					
Inner soil excavation period	Abnormal behavior of diaphram wall and ring beam	gn condition	Geologic condition	eeologic	4	3	н	2	м	<ul> <li>Ground unevenness</li> <li>Lack of geological survey</li> <li>Underestimate in design</li> </ul>	Design	<ul> <li>Make detail geologic survey</li> <li>Considering unevenness of soil layer, eccentric soil pressure is assurned to be 20% of standard soil pressure</li> </ul>	Design dept./Sinotech	1	1	L	1	L
		Propriety of design	ter level							rel fluctuation survey design	Design	<ul> <li>Assume ground water level based on records</li> <li>Assume water level for dry/rainy season</li> </ul>	Design dept Sinotech					
		Pro	Ground water level	Diaphram safety i	5	2	Н	1	М	<ul> <li>Ground water level fluctuation</li> <li>Lack of geologic survey</li> <li>Undcrestimate in design</li> </ul>	Monitor	<ul> <li>Adopt automatic monitor system</li> <li>Pore water pressure gauge</li> </ul>	Design dept. Construction dept	1	1	L	0	L

## **International Standardards**

- ISO3100:2009 Risk Management – Principles and Guidelines, supported by "Practice standard for project risk management" 2009 published by Project Management Institute

## Risk Management – Key Elements

- Risk Manager風險經理
- Risk Register風險登記冊
- Risk Owner/Action Owner 風險管理人 / 風險行動人
- Top ten risks

# Thanks for your attention

